



### Cowessess First Nation Our Renewable Energy Journey

Northwest Community Renewable Energy Conference May 23, 2018



# **Project Overview**

- Cowessess was the proponent of Canada's first wind turbine-battery storage project on Cowessess land outside of Regina
- 1 Megawatt project with a 20-year Power Purchase Agreement with SaskPower
- Enercon E-53 wind turbine with 73m hub height and 53m diameter blades
- Saft lithium-ion batter system housed in two containers
- Cowessess owns the project and executed through a partnership with the Saskatchewan Research Council

# **Project Collaborators**



**Cowessess First Nation** 





### Natural Resources Canada









Power and productivity for a better world™







# **Project Benefits**

- "To develop practical methods of wealth creation that honor First Nations tradition and collective ownership"
- Reduce greenhouse gas emissions
- Reliably increase the amount of renewables on the power grid
- Local contractors for design, supply, integration, and maintenance
- Prove the reliability, durability, and value of windstorage systems over a suite of applications



# Key Project Milestones

#### • 2009

- Project concept developed
- CFN/SRC relationship established
- Funding applications submitted
- Initial work began
- 2010
  - Environmental Assessment Started
  - NAV Canada Appeal Project approved after initial denial
  - Project structure developed
  - Geotechnical study completed
  - Funding agreements Signed
  - Project approved for SaskPower Green Options Partners Program
- 2011
  - Engineering work well underway developing innovative algorithms, site design and single-line diagram
  - Engagement with financial institutions for CFN contribution
  - Initial research on turbine and battery suppliers
    - Release RFPs for equipment
  - Reporting structure developed with all funders



# Key Project Milestones

• 2012

- CFN project equity secured through TLE Schedule L vote
- Finalize wind turbine and battery suppliers
- Project construction underway
- Active project cash flow management
- Roadwork complete, foundation work complete, battery storage system delivered
- 2013
  - Turbine delivered
  - System fully commissioned
  - Project moved to operations
  - Initial revenue being generated by the turbine



## **Construction Milestones**

 July 16, 2012 – Anemometer Tower Installed





 Sept 12, 2012 – Road and site earthworks completed



## **Construction Milestones Cont.**

 Sept. 20, 2012 – Threephase line installed by SaskPower





### Nov. 2013 – Foundation work completed



## **Construction Milestones Cont.**

 Nov. 30, 2013 – Site operations building installed





 Dec 20, 2013 – Batteries and transformer installed



## Construction Milestones Cont.

Mar. 11, 2013 – Turbine construction started





Mar. 16, 2013 – Turbine construction completed



# **Commissioning Milestones**

- Mar. 13, 2013 SaskPower energized the site
- Mar 27, 2013 Wind turbine commissioned
- April 20, 2013 Phase 1 of battery commissioning completed
- May 10, 2013 High Wind & Storage system fully commissioned



### SaskPower Connection



Enercon E-53

# Smoothing Wind Turbine Power Grid Power



 Project reduces volatility to the grid by storing power that can be dispatched on demand



## High Wind and Storage System

Cowessess High Wind Storage Project, Regina, SK 2013-05-13 10:30:09





### **Project Location**



# Project Hurdles

- Complex technical project required ongoing engagement of Council
- Complex project management with a variety of funding sources
- International procurement of multi-million dollar equipment from Germany and the United States
- Managing risks procuring and installing equipment from battery companies
  - Cowessess installation went smoothly (in -30C weather)
- Cowessess election took place one month after installation – new administration tried to sell the project, but legal agreements held up.



# **Opportunity for More**

- After 4 years of operation SRC noted that the turbine is at about 32% efficiency (simply because wind is wind), which mean we produces approximately 660kW per year to sell to SaskPower.
- Results in 340kW of available generation space in our existing 1 MW PPA with SaskPower. Had to "sell" add on to SaskPower.
- SRC and McNair developed new proposal to federal funders for a Solar – Wind – Battery R&D Project. CONTRACT





**OPPORTUNITY** 



(up to 1 MW)

(800kW @ 32% = 660 kW)

(340kW)

# Solar Add On

- Cowessess will add 500 kW of Solar equipment to our wind battery site.
  - 340kW is contracted with SaskPower under existing 1 MW PPA
  - 56 kW is under the Net Metering Program for site offsets
  - 100kW still to be contracted under Small Power Producers Program



# Solar Timeline

- January- March 2017 Funding Proposals
- June 2017 Project Overview with SaskPower
- August 2017 Western Diversification Funding Approval
- Aug Oct 2017 Defining Project Execution with SaskPower
- Sept Dec 2017 Business Planning
- September 2017 RFP for Solar Supply and Install Contractor
- December 2017 Award Skyfire Energy contract
- December 2017 AANDC (LEDSP and CORP) Funding Approval
- March 2018 Equipment Delivered to Site
- May 2018 PPA and GIS Agreements signed with SaskPower
- July August 2018 Construction
- September 2018 Commissioning



# **Project Details**

Costs	Total
Solar Supply and Install, Engineering, Business Services	\$1,558,600
Interconnection Costs	\$800,000
Total	\$2,358,600
Funding Sources	Total
Western Diversification, AANDC (LEDSP & CORP)	\$1,710,000
Cowessess Cash Equity/ Debt (First Nations Bank of Canada)	\$648,600
Total	\$2,358,600

- Cowessess is an independent band, we have developed both the wind/ battery and now the solar projects on our own with the support of our trusted consulting team.
- Internally, Project Director of Economic Development manages the project for Cowessess.

# Solar Project Collaborators



**Cowessess First Nation** 





Aboriginal Affairs and Northern Development Canada



Western Economic Diversification Canada de l'Ouest Canada

Diversification de l'économie







# Solar Add On Hurdles

- Identifying how our existing contract could be amended to include solar.
- Relaying the immediacy of project funding deadlines and getting SaskPower to move quick enough for us to meet funding deadlines.
- Lack of small Solar Procurement Contracts by SaskPower, to utilize all of our available funding and equipment.
- Late in the game \$800,000 Interconnection Upgrade required by SaskPower.
- Pulling together funding sources and meeting aggressive delivery dates.
- KEY TO SUCCESS: Same Internal Project Team from Wind Installation

# Next Steps

- Requirement for Skyfire to hire qualified band members for construction.
- Confirming Balance of Plant subtrades.
- On site Project Execution, Management and Reporting
- Solar press announcement, mid-summer while construction is underway.
- Commission and turn on the revenue meter September.



## **Other Renewable Initiatives**

• Our Leadership's goal is to become one of the greenest First Nation Communities in Saskatchewan.

• Other developments in planning stages:

200 MW Wind - SaskPower RFP (in evaluation)

• Submitted a RFP Response on March 1, 2018 with EDP Renewables Canada and Elemental Energy.

10 MW Solar - First Nation Power Authority RFI (in evaluation)

• Submitted a RFI Response on March 19, 2018 with Elemental Energy.

Low Carbon Economy Challenge (in evaluation)

 Submitted a funding request, May 14, 2018, for 800kW of Community Installed Solar on the home reserve. Goal is to receive 75% federal funding to Net Meter 7 band owned buildings.

### **Questions/ Comments**

